



- ① WATERPROOF DRY SPLICE CONNECTORS
- ② VALVE BOX WITH COVER 12" SIZE
- ③ DIG 3/4" (6-9 DC) REMOTE CONTROL VALVE ASSEMBLY MODEL P53-075
- ④ 155 MESH SCREEN FILTER WITH FLUSH CAP DIG MODEL P10-155 PLASTIC FILTER
- ⑤ 3/4", 30 PSI PRESET PRESSURE REGULATOR
- ⑥ FINISH GRADE TOP
- ⑦ PVC SCH40 FNPT X SLIP COUPLING
- ⑧ PVC MAIN LATERAL LINE
- ⑨ BRICK SUPPORT AT EACH CORNER
- ⑩ PEA GRAVEL SUMP MINIMUM 3"
- ⑪ CONTROL WIRE TO LEIT-2
- ⑫ SWIVEL FITTING (UNION) DIG MODEL 23-004 1"FNPT X 3/4" MNPT
- ⑬ PVC SCH40 MALE ADAPTER
- ⑭ PVC SCH 40 90 DEGREE ELL
- ⑮ SCH 40 TEE
- ⑯ MAIN SUPPLY LINE

HEAD LOSS			
FLOW RATE(GPH)	5	13	18
VALVE HEAD LOSS	3	4	4.5
FLOW RATE(GPH)	5	11	16
FILTER HEAD LOSS	0.2	2.0	4.3
FLOW RATE(GPH)	4	13	15
REGULATOR HEAD LOSS	2	7	8

② REMOTE CONTROL ZONE ASSEMBLY FOR DRIP SYSTEM  
 A53-075, 3/4" DC (6-9 VOLT) VALVE WITH 155 MESH FILTER  
 AND 30 PSI PRESET PRESSURE REGULATOR

NOT TO SCALE  
 DATE: 1-26-09